	Description Of Item	Unit	No	L	B	D	Qty	Rate	Amount
	...lying and fixing of porcelain fuse channel with cut-out on existing / new wooden ...nel using neccesary nuts, bolts and washers etc., complete P-32, I-3 (b), PWD ...LECT ...AL SR 2010-11.								(4)
		Nos					50.00	219.00	10950.00
19	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. Noll KBS 2.1.C/2.9.4/2.18/2.19 (Pg. No-5, I.No2.4)								
		Cum	2	600.00	0.60	0.75	540.00	190.80	103032.00
20	Providing and installing at site of work P.V.C pipees including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not leass than 15 cms with gravel or selected earth available from the excavation etc., complete PVC pipes of 6kg/Sqm 75mm Dia.(Page NO-14, iTEM no-3.4.2 (b), of PRE SR 2011-12).						685 Rmt	157.00	107545.00
		Rmt	(2) 1	685 Rmt 600.00			600.00	117.00	70200.00
21	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. Including cost of all labour complete as per specification. (Pg. No-6, I.No-2.11)						308.25		15847.00
		Cum	Omitted SNO 19				540.00	51.41	27761.00
22	Transportation of pumping machineries PRE SR 2011-12 PG 51/10.3.19						4.00	850.00	3400.00
23	Erection of Pumping machineries PRE SR 2011-12 PG 51/10.3.20						4.00	850.00	3400.00
24	Miscellanious and rounding off KRDCL charges 10+1=11%						LS	907.00	990000.00
25	Necessary							TOTAL	1000000.00

(Rupees Ten Lakhs Only)

CERTIFICATE:-

1 The Work spot has been inspected and the work is found to be necessary
2 The Estimate is prepared as per the PW,P & IWTD -SR-2012-13
3 The Provision made in estimate are adequate and essential.
4 This area comes under BBMP limits.
5 Approved Data Rate Sheet Enclosed

A/s.

Assistant Engineer,
Ward-14
B.B.M.P.

Asst. Exe. Engineer
T.Dasarahalli Sub-Division
B.B.M.P.

Exeutive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

ನಂ JC(DH)AS 105/13-14 ದಿನಾಂಕ : 19/07/13
ರೂ. 10.00 lakhs (Rupees Ten lakhs only)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
Page No. 189
Sl. No. 105

ನಂ.EE/DD/15/47/13-14 ದಿನಾಂಕ : 31/7/2013
ರೂ. 10.00 lakhs Rs. Ten lakhs only
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ